

**PROJECT NAME: DRFAWA Reconstruction Works - AGRN 933**

<b>MAJOR WORKS</b>	<i>SLK (From)</i>	<i>SLK (To)</i>	<i>Description</i>		
Mt. Shadforth Road	1.29	1.36	Embankment Slippage - Requires rebuilding, stabilisation of the embankment, and a guardrail		
Scotsdale Road (Roundabout)	1.25	1.25	Requires removal of the asphalt and replacement		
Hollings Road (Retaining Wall)	0.4	0.4	Requires resetting the retaining wall		
<b>MINOR WORKS</b>	<i>SLK (From)</i>	<i>SLK (To)</i>	<i>Description</i>	<i>Degree</i>	<i>Reinstatement Scope</i>
Atkinson Road	0.48	0.61	Drain Scour	Medium	Drain Reinstatement
Atkinson Road	0.61	0.63	Drain Silt/Debris	Minor	Drain Silt/Debris Removal - Minor
Atkinson Road	0.48	0.61	Shoulder Scour	Heavy	Shoulder Reconstruct
Atkinson Road	0.09	0.1	Drain Scour	Minor	Drain Reshape
Barnes Road	0.71	0.76	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Barnes Road	6.06	6.11	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Barnes Road	0.71	0.76	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Barnes Road	6.06	6.11	Drain Scour	Medium	Drain Reinstatement
Barnes Road	0.71	0.71	Blocked Culvert		Clean out culvert and remove silt
Barnes Road	6.06	6.06	Blocked Culvert		Clean out culvert and remove silt
Board Road	0.35	0.47	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Board Road	0.35	0.47	Drain Scour	Medium	Drain Reinstatement
Board Road	0.35	0.47	Drain Silt/Debris	Medium	Drain Silt/Debris Removal - Medium
Board Road	0.35	0.35	Blocked Culvert		Clean out culvert and remove silt
Boat Harbour Road	1.65	1.69	Gravel Surface Wash off		Medium Grade
Boat Harbour Road	1.64	1.65	Drain Silt/Debris	Medium	Drain Silt/Debris Removal - Medium
Boat Harbour Road	1.64	1.65	Drain Silt/Debris	Medium	Drain Silt/Debris Removal - Medium
Boat Harbour Road	1.65	1.65	Blocked Culvert		Clean out culvert and remove silt
Burke Place	0.2	0.22	Pavement Scour (Sealed)	Heavy	Reconstruct Seal & Pavement
Burke Place	0.2	0.22	Drain Scour	Heavy	Drain Reconstruct
Burke Place	0.2	0.2	Blocked Culvert		Clean out culvert and remove silt
Conspicuous Beach Road	1.7	1.72	Gravel Surface Wash off		Medium Grade
Crusoe Beach Road	1.12	1.16	Pavement Scour (Unsealed)	Medium	Gravel Resheet
East River Road	2.7	3.2	Drain Scour	Medium	Drain Reinstatement
East River Road	2.7	3.2	Drain Silt/Debris	Medium	Drain Silt/Debris Removal - Medium
East River Road	2.05	2.15	Drain Scour	Heavy	Drain Reconstruct
Ficifolia Road	0.2	0.54	Drain Scour	Medium	Drain Reinstatement
Ficifolia Road	0.2	0.54	Drain Scour	Medium	Drain Reinstatement
Ficifolia Road	0.54	0.69	Drain Silt/Debris	Medium	Drain Silt/Debris Removal - Medium
Ficifolia Road	0.54	0.69	Drain Silt/Debris	Medium	Drain Silt/Debris Removal - Medium
Ficifolia Road	0.685	0.695	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Ficifolia Road	0.685	0.695	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Ficifolia Road	0.535	0.545	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Ficifolia Road	0.535	0.545	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Ficifolia Road	0.54	0.54	Blocked Culvert		Clean out culvert and remove silt
Ficifolia Road	0.48	0.48	Blocked Culvert		Clean out culvert and remove silt
Ficifolia Road	0.34	0.34	Blocked Culvert		Clean out culvert and remove silt
Freds Road	0.65	0.7	Shoulder Scour	Heavy	Shoulder Reconstruct
Happy Valley Road	5.1	5.14	Drain Scour	Medium	Drain Reinstatement
Happy Valley Road	5.14	5.14	Blocked Culvert		Clean out culvert and remove silt
Happy Valley Road	5.1	5.145	Drain Silt/Debris	Medium	Drain Silt/Debris Removal - Medium
Happy Valley Road	6.64	6.73	Drain Scour	Medium	Drain Reinstatement
Happy Valley Road	6.64	6.73	Drain Silt/Debris	Medium	Drain Silt/Debris Removal - Medium
Happy Valley Road	6.64	6.64	Blocked Culvert		Clean out culvert and remove silt
Harewood Road	3.37	3.47	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Harewood Road	3.9	3.95	Pavement Scour (Unsealed)	Medium	Gravel Resheet

**16 NOVEMBER 2021 - ATTACHMENT 9.1.6a**

**PROJECT NAME: DRFAWA Reconstruction Works - AGRN 933**

Hazelvale North Road	1	1.02	Pavement Scour (Unsealed)	Heavy	Pavement Reconstruct
Howe Road	1.6	1.92	Drain Scour	Minor	Drain Reshape
Kernuts Road	1.8	1.8	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Kernuts Road	4.46	4.46	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Kernuts Road	5.02	5.02	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Kernuts Road	5.3	5.3	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Kernuts Road	6.07	6.07	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Kernuts Road	6.23	6.23	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Kernuts Road	6.55	6.55	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Lights Road	1.01	1.11	Pavement Scour (Unsealed)	Minor	Heavy Grade
Lights Road	1.11	1.21	Pavement Scour (Unsealed)	Minor	Heavy Grade
Mooney Valley Road	0.2	0.22	Shoulder Scour	Medium	Shoulder Reinstatement
Nunn Road	2.72	2.77	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Parker Road	1.07	1.08	Shoulder Scour	Heavy	Shoulder Reconstruct
Pierce Street	0.01	0.1	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Pierce Street	0.01	0.1	Drain Scour	Minor	Drain Reshape
Pierce Street	0.01	0.01	Blocked Culvert		Clean out culvert and remove silt
Pitt Road	0.7	0.7	Blocked Culvert		Clean out culvert and remove silt
Pitt Road	1.7	1.7	Blocked Culvert		Clean out culvert and remove silt
Pitt Road	1.7	1.75	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Privett Road	0.24	0.28	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Redman Road	0		Blocked Culvert		Clean out culvert and remove silt
Roberts Road	0.61	0.64	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Sunny Glen Road	0.09	0.12	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Sunny Glen Road	3.06	3.46	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Sutton Road	1.87	1.89	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Walter Road	1.65	1.75	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Wentworth Road	1.51	1.53	Pavement Scour (Unsealed)	Medium	Gravel Resheet
Wentworth Road	1.45	1.55	Drain Silt/Debris	Medium	Drain Silt/Debris Removal - Medium
Wentworth Road	1.45	1.5	Drain Scour	Medium	Drain Reinstatement